

EV 700



9 Week Flower Cycle Light Schedule (Quantity)

	SPECTRUM			CANOPY TO LED DISTANCE	PPFD	DLI - 12 HOURS (AVERAGE DLI)
	660 NM	2700 K	6500 K			
Week 1	25%	60%	70%	24"	320 - 390	15.5
Week 2	40%	75%	85%	24"	380 - 470	18.3
Week 3	65%	90%	100%	24"	440 - 550	21.6
Week 4	90%	100%	100%	24"	460 - 570	22.4
Week 5	100%	100%	100%	18"	570 - 690	27.2
Week 6	100%	100%	100%	12"	660 - 800	31.5
Week 7	100%	100%	100%	12"	660 - 800	31.5
Week 8	100%	100%	100%	12"	660 - 800	31.5
Week 9	100%	100%	100%	12"	660 - 800	31.5

NOTES: _____
